

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 32W	17
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 23 T 48N R 32W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 5 05/19/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(17) Corner common to Sections 14-15-22-23. 1971 - Reestablished by A.O.Enger RLS by double proportionate measurement to the original record. Set 1"IDx36" I.pipe with 4" aluminum cap. B.Spruce 4" S56W 36.6', B.Spruce 8" S21W 15.7', W.Pine 24" N17W 55.0'.

(5-Sec. 23) North 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(17) Found the 1971 monument in good condition and at record bearing and distance from two remaining NBTs, in good condition with blazes overgrown. Verified the position of the monument with respect to Section corners 2 miles north, 1 mile east, 1 mile south, and Quarter corner 1/2 mile west and accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(5-Sec. 23) Established the corner midway and on a straight line between Quarter corner 1315.47' north and Center of Section 1315.47' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(17) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 30" W.Pine N12W 56.0' 1971 NBT
 8" B.Spruce S60W 36.9' do
 5" Sugar N41W 24.5' mrkd "S15 NBT"
 7" B.Spruce S88E 6.55' "S23 NBT"
 Sq'd cedar post adjacent. Bearings magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Spruce N47E 12.05' mrkd "1/16S BT"
 7" Balsam S76E 10.55' do
 8" Sugar S46W 4.3' do
 5" Maple N17W 27.1' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/16/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division