

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 32W	K8
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T 23 R 48N R 32W	14
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on K8 05/24/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K8) Quarter corner common to Sections 23 and 24. 1852 - Established by Guy H. Carleton Deputy Surveyor midway and on the Section line between Section corners 40.04 chains north and south. Set post. Sugar 12 S39E 12 links, Fir 10 N68W 21 links. 1971 - A.O.Enger RLS reestablished the corner by single proportionate measurement to the original record between Section corners. Set 1"ID I.pipe with 4" aluminum cap. W.Birch 16 S65E 2.2', R.Maple 9 N04W 36.3'. 2001 - The undersigned recovered the 1971 monument and made additional witnesses. No attempt was made in 2001 to verify the validity of the 1971 position.

(14-Sec. 23) South 1/16 corner between Sections 23 and 24. 1971 - Monumented in 1971 by A.O.Enger RLS. Set 1"IDx36" I.pipe with 4" alum. cap midway and on line between corners 19.995 chains north and south.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K8) Recovered the 1971 monument in accord with the 1971 and 2001 witnesses. Measurements made this date to Section corners north and south show that the position of the monument is grossly erroneous being 66' west of the position intended in 1971. Removed the 1971 monument and reestablished the corner midway and on the section line between Section corners 2633.98' north and south.

(14-Sec. 23) The 1971 monument was recovered in good condition but was not accepted. The monument occupies a grossly erroneous position N88W 97.9' from the position intended in 1971. Removed the 1971 monument and established the corner midway and on the Section line between Quarter corner 1316.99' north and Section corner 1316.99' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Sugar N08W 36.1' mrkd "1/16S NBT"
 7" Balsam N88E 37.9' do
 7" Sugar S36W 50.5' do
 5" Sugar N85W 63.5' do
 Sq'd cedar post adjacent. Bearings are magnetic.

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Sugar N08E 12.4' mrkd "1/16S BT"
 5" Maple N82E 25.75' do
 9" Sugar S20E 18.1' do
 19" Sugar S57W 4.0' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/16/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division