

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43N</u> N. S., R. <u>33</u> W.	<u>1-2, 1-1</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>43</u> N. S., R. <u>33</u> E. W.	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
LOT NO. _____, RECORDED PLAT _____		
PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1: Original monument and accessories not found. Found 1" I.D. x 36" iron pipe set by unknown person. Two old location posters on 14" Sugar N20°W, 3.8 ft.
- 2: Original monument and accessories not found.
- 3: Not set on original survey nor subsequently apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- 1: Re-established 5-20-76 at location of pipe. Pipe used as corner for many years and fits good with other corners in area.
- 2: Re-established 5-20-76 on line between section corners north and south.
- 3: Established 5-20-76 on line between section corner south and 1/4 corner north.

**Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
  - 6" Sugar N50°W 14.6 ft. S34, NBT
  - 7" Sugar N47°E 15.7 ft. S35, NBT
  - 8" Sugar S18°E 11.7 ft. S 2, NBT
- 2: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
  - 4" Maple N34°W 5.7 ft. S 3, NBT
  - 10" W. Birch N42°E 20. ft. S, NBT
  - Squared 3" Cherry N9°E 1.6 ft.
- 3: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
  - 14" Sugar S50°E 7.3 ft. 1/16 S, BT
  - 9" Spruce S69°W 11.0 ft. 1/16 S, BT


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

STATE OF MICHIGAN REGISTRATION NO. \_\_\_\_\_

OF STATE AND UNITED STATES AGENCIES: \_\_\_\_\_

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

RECEIVED AND SIGNED BY Keith L. Sackett DATE June 28, 1976  
MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett (SEAL)



MICHIGAN REGISTRATION NO. 19036