

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 N.R. 33 W


Baraga COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 27-28-33-34

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/3/65 with Forester Stevens

WITNESSES TO CORNER..... 20" W. Pine (S27 NBT), N 50° E, 28 Lks.



14" W. Pine (S28 NBT), N 81° W, 41 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from 2 Original BT's (W. Pine 24", N 21° W, 7 Lks.)
and (W. Pine 20", S 23° E, 35 Lks.). Both are stumps cut above upper faces.
Scribe marks on both Lower and Upper faces.

SURVEYOR'S SEAL

Frank J. Bray
SIGNED Frank J. Bray DATE 2/11/1966
REGISTERED LAND SURVEYOR