

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

*Baraga*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY-----	T. 48 N. <del>XX</del> R. 33 <del>XX</del> W.	A7
2. PROPERTY CONTROLLING IN SECTION-----	T.----- N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION-----	T.----- N. S. R. E. W.	
4. LOT NO.-----, RECORDED PLAT-----		
5. PRIVATE CLAIMS-----		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on March 2, 1970, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Original post or accessories not found. Found an iron pin buried in center of county road, as placed by unknown party.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Accepted road centerline as marking the latitude of the corner, by common report. Measured southerly to original section corner A9; found it to bear  $S0^{\circ}27'17''W$  81.514 chains from corner A7. (Bearing by solar observation). As distances from each of these corners to the shores of Vermilac Lake between them checks closely with original record distance, I concluded that the 1.514 chains difference from the record total distance results from an error in original measurement or computation. My measurement is directly across lake on the ice. The evidence seems sufficient to support the found iron pin, so accepted it for the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Did not replace the monument found. Exact dimensions of monument not known. Witnesses as follows:

- Cedar 5  $S18\frac{1}{2}^{\circ}W$  (mag.) 52.3 ft. "S24, NBT"
- Cedar 4  $S18^{\circ}E$  (mag.) 34.8 ft. "S19, NBT"
- 1" iron pipe  $S2^{\circ}W$  (mag.) 33.13 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE March 14, 1973

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger**

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581