

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. 33 R. 33 W.	J 9 & J 11
2. PROPERTY CONTROLLING IN SECTION 26	T. 48 N. 33 R. 33 W.	15a
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 27 1970, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners J9 & J11: Original posts or accessories not found. At J9, found a 5.8 ft. length of angle iron placed vertically in ground at site of an old, rotted wood post. At J11, found a 1½" I.D. x 36" iron pipe in place. Parties who set monuments not known; they appear to have been in place for many years.
Corner 15a: Original meander post or its accessories not found. Found a 1" I.D. x 43" iron pipe on shore of King Lake, purporting to be the M.C.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J 9: Monument appears to be consistent with natural features to west called for in original field notes, and is 119.61 ch. E of nearest known corner to W, having original record distance of 119.98 ch. It bears N0°27'10"W 79.929 ch. from S 1/4 cor. of Sec. 26. Evidence seems sufficient to accept monument as the corner.
Corner J11: Accepted monument as found. Appears consistent with natural features to W. Lies N89°25'20"E 29.927 ch. from monument at M.C. on E. shore of King Lake, compared to record distance of 29.82 ch.
Corner 15a: Accepted monument as found, as it, in conjunction with J9 and J11, is reasonably consistent with the record of the original survey. All corners have been long used in adjacent property descriptions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. iron pipe with 4" aluminum cap.

Witnesses for Corner J 9: Sugar Maple 9 S68°W (mag.) 20.1 ft. "1/4S, NBT"
 Sugar Maple 8 S20°E (mag.) 29.0 ft. "1/4S, NBT"
Witnesses for Corner J11: Sugar Maple 10 S20°E (mag.) 8.4 ft. "1/4S, NBT"
 Red Maple 11 N47½°W(mag.) 26.9 ft. "1/4S, NBT"
Witnesses for Corner 15a: Red Pine 12 South (mag.) 8.7 ft. "MC, NBT"
 Red Pine 10 N86°E (mag.) 19.4 ft. "MC, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 14, 1973

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581