

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 48 N. R. 33 W.	E7
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **May 27** 19**70**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Original post or its accessories not found. Found an old squared cedar post in place, as set by unknown surveyor.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Many very old blazes facing the post on nearby trees. Northern Paper Mills location tag reports this as the corner. By aerial photo examination, this location fits the probable corner area. Therefore, accepted the post as probably being at or near the original corner location.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**1" I.D. x 36" iron pipe with 4" aluminum cap.**

- Cedar 9 N72°W (mag.) 27.0 ft. "S17, NBT"
- Cedar 8 S 6°E (mag.) 21.5 ft. "S21, NBT"
- B. Spruce 8 N48°E (mag.) 24.2 ft. "S16, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Arthur O. Enger* DATE **March 14, 1973**  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**