

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. XX R. 33 XX W.	G7, G6
2. PROPERTY CONTROLLING IN SECTION 16	T. 48 N. XX R. 33 XX W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. RECORDED PLAT.		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 5, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of Law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner 16: **Not set on original survey nor subsequently apparently.**
 - Corner G7: **Original monument and accessories not found. Found iron pipe set by unknown person.**
 - Corner G6: **Original monument and accessories not found. Found two old pipes and one old square post.**
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner 16: **Established midway and on line between corners east and west.**
 - Corner G7: **Restored at iron pipe. Fits good with corners north and south. Not good with corner west.**
 - Corner G6: **Restored at 1½" pipe.**
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|--|---|
| Corner 16: Set 1" I.D.x32" iron pipe with 4" alum. cap.
6" Sugar N42E 6.1 ft. 1/16S,BT
9" Sugar S9W 18.0 ft. 1/16S,BT
7" Sugar N40W 18.4 ft. 1/16S,BT | Corner G6: 1½" I.D. iron pipe
4" Maple S57W 8.8 ft. ¼S,NBT
5" Maple N39W 16.0 ft. ¼S,NBT
7" Ash N84E 28.2 ft. ¼S,NBT |
|--|---|
- Corner G7: ½" I.D. iron pipe
 11" Sugar N61E 15.0 ft. S15,NBT
 9" Sugar S19W 13.0 ft. S21,NBT
 9" Sugar N61W 37.0 ft. S16,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Michigan Dept. of Natural Resources
 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006