

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:		LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48	N. R. 33 K. W.	F7
2. PROPERTY CONTROLLING IN SECTION	16 T. 48	N. R. 33 K. W.	14, 15
3. MISCELLANEOUS PROPERTY IN SECTION		N. R. 33 K. W.	
4. LOT NO. ...., RECORDED PLAT. ....			
5. PRIVATE CLAIMS .....			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Keith L. Sackett**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on **March 5, 1981**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner F7: Original monument and accessories not found.
  - Corner 14: Not set on original survey nor subsequently apparently.
  - Corner 15: Not set on original survey nor subsequently apparently.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner F7: Restored midway and on line between corners east and west.
  - Corner 14: Established midway and on line between corners north and south.
  - Corner 15: Established midway and on line between corners east and west.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |   |  |
|---|--|
| <p>Corner F7: Set 1" I.D.x32" Iron Pipe with 4" alum. cap.<br/>                     5" Balsam N12E 2.8 ft. 1/8S,NBT<br/>                     10" Spruce N51W 19.7 ft. 1/8S,NBT<br/>                     10" Balsam S20W 26.6 ft. 1/8S,NBT<br/>                     Squared 3" Balsam south 2.2 ft.</p> <p>Corner 14: Set 1" I.D.x36" iron pipe with 4" alum. cap.<br/>                     14" W. Birch N72W 12.8 ft. 1/16S,BT<br/>                     6" Maple N6E 9.3 ft. 1/16S,BT<br/>                     16" Maple S61E 19.1 ft. 1/16S,BT</p> | <p>Corner 15: Set 1" I.D.x32" iron pipe with 4" alum. cap.<br/>                     5" Spruce N45E 11.2 ft. 1/16S,BT<br/>                     10" Spruce S70W 20.2 ft. 1/16S,BT<br/>                     10" Spruce N60W 23.3 ft. 1/16S,BT</p> |
|---|--|

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Keith L. Sackett* DATE **1-26-82**  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **19006**