

52

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga

	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 33W	A10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Nov 07 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Quarter corner on the Range Line between R33W and R34W and common to Sections 30 T48N-R33W and 25 T48N-R34W. Corner established in 1846 by Austin Burt : " North on East side Section 25...40.00 Set Spruce Post qr. Section Corner. Spruce 6 S63E 24, Tamarac 7 N64W 14...80.00 Set Spruce post corner of Sections 24 & 25...". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Re-monumented the corner at the position of the original corner post, and at record bearing and distance from the remains of the two original bearing trees, both recovered. The post was recovered rotted off at ground level but well preserved below ground, in waterlogged sphagnum moss. It is now a 3" dia. spruce post point in excellent condition. The 6" spruce bearing tree is now a 3" wide by 12" long stump fragment with old blaze, overgrowth, axe mark, and bottom of measuring notch plainly visible. The tamarack bearing tree was recovered as a mound of distinctly dark colored organic material surrounded by lighter colored moss. The two adjacent section corners on the range line, both perpetuated original corners, were found to be S00 deg. 09 min. 25 sec. W, 39.869 ch., and N00 deg. 11 min. 13 sec. E, 39.810 ch. distant (bearings referenced to astronomic north). At the position of the post, I placed a 1" I.D. x 32" iron pipe, capped with a 4" dia. cast aluminum MDNR tablet, stamped "Michigan Dept. of Natural Resources, T48N R33-34W, 1/4 34/33, PSJ3986, 11-7-1996".


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" ID iron pipe with 4" MDNR aluminum cap. Blazed and scribed the following new bearing trees:

6" spruce N24W 8.6' "1/4S NBT"
8" spruce N87E 9.0' "1/4S NBT"
8" spruce S18E 13.3' "1/4S NBT"
8" spruce S33W 15.1' "1/4S NBT"

Placed a 3" squared sugar post adjacent.
Bearings are magnetic.

New bearing trees are marked with a 8H blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date Dec. 18, 1996

For the Michigan Department of Natural Resources - Forest Management Division