

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga

(County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 33W	A5
	T 48N R 33W	C5
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on August 26, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A5) Section corner common to Sections 7-18 T48N-R33W, and 12-13 T48N-R34W. Original corner established in 1846 by U.S. Deputy Surveyor Austin Burt. BTs: Sugar 12 N31 1/4E 21, Sugar 20 N53 1/2W 43. Subsequent BTs established in 1852 during township subdivision: Sugar 18 S68W 27, Ironwood 8 N67E 21. Found no subsequent record.

(C5) Section corner common to Sections 7-8-17-18. Original corner established in 1852 by U.S. Deputy Surveyor Francis S. Houck. BTs: Cedar 16 N26W 48, Y. Birch 16 S46E 29. Original notes show: 1) north 28.00 ch Top of ridge and ledge 50 C E+W; 2) west 1.22 ch Brook 3 CMM; 3) south .80 brook 3 C west; 4) south 64.5 top of ridge and ledge 50 C ESE. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A5) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner. Reestablished the corner by single proportionate measurement to the original record between monumented corners 2632.78' south and 5265.56' north. At the position for the corner I placed a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. A squared post, apparently a forester's approximate corner, was found N49E, 18.1' from the monument placed. Several old blazes face the post, as well as an old Celotex location poster with numerous names and dates, and marked "Approx. corner".

(C5) Original post and accessories not recovered. Found no monumentation at the corner position. Although the brook referenced above can be identified to the northwest and southeast of the corner location, it has been obliterated to the south and west by the marshy clearing in which the corner falls. Found no acceptable evidence of the location of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between monumented corners 4962.17' west (4964.5 U.S.), 5275.64' north (5280 U.S.), 5285.42' east (5287.9 U.S.), and 5275.64' south (5280 U.S.). From this position, well defined ridges/ledges north and south check with the original record. Recovered a squared post with a Celotex corp. location poster dated 1956 affixed, in a north-south fence line 18' east and 23' north of the corner position. At the position for the corner, I placed a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A5) Set a 1" pipe with a 4" MDNR cap. (C5) Set a 1" pipe with a 4" MDNR cap.

Blazed and scribed the following new bearing trees: Blazed and scribed the following new bearing trees:

13" Sugar S10W 3.2'	"S13 NBT"	5" Balsam S45W 9.5'	"S18 NBT"
10" Sugar S10E 18.4'	"S18 NBT"	8" Balsam N32W 15.4'	"S7 NBT"
10" Sugar N87E 23.2'	"S7 NBT"	10" Y. Birch N29E 35.5'	"S8 NBT"
12" Sugar N33E 19.5'	"S7 NBT"	8" Cedar S34E 59.0'	"S17 NBT"
6" Sugar N44W 16.8'	"S12 NBT"	Placed a 4" squared cedar post, scribed	
10" Sugar with Celotex L.P. N55E 26.2'		7-8-17-18, 1' north of the corner.	



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 9-1-93