

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Baraga

(County)

Located In:

Corner Code #

**1. Public Land Survey**

T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____

**2. Property Controlling in Section**

S	<u>31</u>	T	<u>48N</u>	R	<u>33W</u>	<u>2</u>
S	<u>31</u>	T	<u>48N</u>	R	<u>33W</u>	<u>1</u>

**3. Miscellaneous Property in Sec.**

S	_____	T	_____	R	_____	_____
S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1 Feb 13 2002

2 Feb 12 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11	●	●												
12	31			32			33			34			35	36
13														

**A. Description of original monument and accessories and/or subsequent restoration:**

(2-Sec. 31) East 1/16 corner between Sections 30 and 31. Established in 1987 by K.L.Sackett, RLS, midway and on line between Section and 1/4 corners. 1"IDx36" iron pipe with plastic cap. 4" sugar N59W 14.1', 5" sugar S54W 24.0', 6" sugar N15E 17.9'.

(1-Sec. 31) West 1/16 corner between Sections 30 and 31. Established in 1987 by K.L.Sackett RLS, by proportion between Section corner west and Quarter corner east. 1"IDx36" iron pipe with plastic cap. 7" Cedar N74W 17.9', 8" Cedar N34E 11.4', 9" Cedar S30W 42.1'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(2-Sec. 31) Recovered the 1987 monument at record bearing and distance from the 1987 accessories. This monument does not occupy the intended position due to a 1987 error in calculation. I removed the 1987 monument and placed a new monument midway and on a line of mean true bearing between Section corner 1318.04' east and Quarter corner 1318.04' west.

(1-Sec. 31) Recovered the 1987 monument at record bearing and distance from the 1987 accessories. This monument does not occupy the intended position due to a 1987 error in calculation. I removed the 1987 monument and placed a new monument at the proportionate position, on a line of mean true bearing between section corner 1124.95' west and 1/4 corner 1318.04' east.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:  
 9" Cedar N62E 16.9' "1/16S 81"  
 the 1987 wits remeasured:  
 10" Cedar N07E 12.5' do  
 10" Cedar S42W 42.7' do  
 9" Cedar N69W 24.6' do  
 Sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:  
 4" Sugar S33E 19.7' "1/16S 81"  
 the 1987 wits remeasured:  
 6" Sugar S74W 26.0' overgrown blazes  
 4" Sugar N51W 20.8' "1/16S 81"  
 8" Sugar N02E 22.5' do  
 Placed a squared B.Spruce post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 4/18/02