

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>48N</u> R <u>33W</u>	<u>K7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>48N</u> R <u>33W</u>	<u>14</u>
	S <u>13</u> T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

K7 Oct 29 2003
 14 Nov 05 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K7) Corner common to Sections 13-14-23-24. 1852: Established by Francis Mouck, D.S.: N89 deg. 57'W corrected between Secs 13&24...80.00 Set post corner of Sections 13-14-23-24. W.Pine 14 N35W 47 links, Tam 14 S37E 22 links.
 (14-Sec. 13) South 1/16 corner between Section 13 T48N-R33W and Section 18 T48N-R32W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) Remonumented the corner at the position of the original post, now a 2" dia. x 6" long point found with axe mark plain, and recovered at record bearing and distance from the rotten stump remains of both original bearing trees, found with no markings visible. Distances North to an original 1/4 corner is 2635.23' (2640 R) and East to a reestablished Section corner is 5288.45' (5280' R). From the corner remonumented, found a 1/2" ID iron pipe, the upper portion rotted off at the surface of the water table, S7E 28.4' distant, placed by persons unknown.
 (14-Sec. 13) Established the corner midway and on a straight line between Quarter corner 1311.60' North and Section corner 1311.60' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 3" W.Pine S39W 36.4' "S23 NBT" 8" Cedar N77W 64.9' "S14 NBT" 6" dbl B.Spruce N60W 59.6' do 7" Cedar N50W 78.3' do Made the monument firm in a mound of rock. Bearings are magnetic. Distances are to nail with tag.	(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 13" Cedar N24E 13.4' "1/16S BT" 7" Cedar N74E 27.4' do 5" B.Ash S86W 10.7' do 9" Cedar N52W 26.0' do Set a squared cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/13/03

For the Michigan Department of Natural Resources, Office of Land and Facilities

