

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 33W	L7
	T R	
	T R	
	S T R	
2. Property Controlling in Section	S 24 T 48N R 33W	14
	S T R	
3. Miscellaneous Property in Sec.	S T R	

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

14 Nov 04 2003
 L7 Nov 05 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L7) Quarter corner common to Sections 13-24. 1852: Established by Francis Houck, DS: N89 deg. 57'W corrected between Secs. 13 & 24...40.00 Set qr. post. Y.Birch 10 N42W 20 links, Cedar 12 S4E 29 links.
 (14-Sec. 24) South 1/16 corner between Sections 24 T48N-R33W and 19 T48N-R32W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L7) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 2644.22' east and west. I observed the true bearing of the line M7-K7 to be N89 deg. 45'W.
 (14-Sec. 24) Established the corner midway and on a straight line between Section corner 1311.60' South and Quarter corner 1311.60' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 10" Cedar N25E 17.4' "1/4S NBT" 5" B.Ash S85E 10.8' do 5" B.Ash N81W 7.1' do 17" Cedar N19W 62.6' do Set a squared cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 4" Balsam N14W 9.0' "1/16S 8T" 5" W.Pine N78E 10.4' do 5" W.Spruce S47W 36.3' do 5" W.Spruce S89W 35.4' do Set a squared spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/13/03