

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>48N</u> R <u>33W</u> | <u>G10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 06 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G10) Quarter corner common to Sections 27-28. 1851 - Established by Francis Houck, Deputy Surveyor: N17'W Corrected between Sections 27 & 28 ...40.09 Qr. post. Fir 10 N53W 23 links, W.Pine 18 S35E 7 links. ...80.18 Section Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G10) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record between Section corners 2638.82' north and south. The corner position falls on a rock knoll. The monument was driven to refusal and made firm in a 3 ft. diameter by 1.5' high mound of rock.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G10) Set 1"IDx32" I.pipe with 4" alum.
 MDNR cap. Set measuring nails in:
 11" W.Pine N14E 47.2' mrkd "1/4S NBT"
 5" Cedar N66E 14.6' do
 5" Cedar S89E 9.8' do
 5" Cedar S71W 40.9' do
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/05