

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 48N R 33W

H11

T _____ R _____

T _____ R _____

S _____ T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims

Jun 22 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H11) Quarter corner common to Sections 27 and 34. 1851 - Established by Francis Houck, Deputy Surveyor: S89 deg. 45'N Corrected between Sections 27 and 34 ...34.46 Set Meander Post ...40.165 Set Qr. Post Tamarack 10 N88 1/2W 33 links, Spruce 8 S21E 8 links. ...80.33 Section Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H11) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement and on line between Section Corner 2646.41' West and reestablished Meander Corner 375.90' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H11) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
6" B.Spruce N66E 20.9' wrkd "1/4S NBT"
7" Cedar S27E 15.9' do
6" Cedar S29W 18.6' do
10" Cedar N38W 14.7' do
Set sq'd Cedar post adjacent. Bearings
are magnetic. Distances are to nail
with tag.

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/05

For the Michigan Department of Natural Resources, Office of Land and Facilities