

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 33W	I9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

May 25 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(I9) Corner common to Sections 22-23-26-27. 1851 - Established by Francis Houck, Deputy Surveyor: North corrected between Sections 26 & 27 ...47.67 Over Lake and set meander corner ...80.00 Corner of Sections 22-23-26-27. Spruce 4 N12W 4 links, Tamarack 5 S11E 30 links. N11'W corrected between Sections 22 & 23 19.75 Intersect lake. 1931 - US GLO survey of Island in King Lake (Government Lot 4) by Jos. C. Thoma, U.S.C. Engineer, gives a bearing and distance from AMC on G.L. #4 to I9 of N13 deg. 20'E, 38.66 chains.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I9) The original post and accessories were not recovered. Found no physical evidence on the ground of any subsequent perpetuation of the corner. Reestablished the corner at record distance south of south edge of lake 19.75 chains north, at record distance north of north edge of lake 32.33 chains south, and by proportionate measurement to the original record between Section corner 69 5269.29' West (rec. 80.10 ch.) and Quarter corner J9 2623.46' East (rec. 39.88 ch.). From the position thus established, the 1931 AMC on G.L.#4 was found S13 deg. 01'35"W (true), 38.535 chains distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I9) Set 1"IDx60" I. pipe with 4" alum.
 MDNR cap made firm with wooden hubs.
 Set measuring nails in:
 2" Tamarack N25E 35.4' mrkd "S23 NBT"
 2" Tamarack N63E 34.6' do
 2" Tamarack S72E 34.1' "S26 NBT"
 3" Tamarack N78W 14.3' "S22 NBT"
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/05

For the Michigan Department of Natural Resources, Office of Land and Facilities