

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>48N</u> R <u>33W</u>	<u>K3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>48N</u> R <u>33W</u>	<u>9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

9 Oct 26 2005
 K3 Oct 25 2005

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Corner common to Sections 1-2-11-12. 1975 - Recorded by K.L.Sackett RLS: "Found 1 1/2"x24" iron bolt with 2"x2" square head witnessed by Highway Department in 1944. Reestablished 4-29-1975 at location of iron bolt. Set 1"IDx24" iron pipe with 4" aluminum cap 28.5 ft. south of C/L US41. 10" Cedar S75E 51.2', 8" Birch S47W 41.2'.
 (9-Sec. 2) East 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) Found the 1975 monument in good condition and at record bearing and distance from the 1975 witnesses, both in good condition. The monument cap is illegible due to corrosion and dirt. Left the monument in place and made new witnesses as described below.
 (9-Sec. 2) Established the corner midway and on a straight line between Quarter corner 1319.05' east and Center of Section (unmonumented) 1319.05' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 15" Cedar S69E 51.6' overgrown blazes * 10" W.Birch S54W 41.4' old marks * 8" Cedar S07E 31.8' mrkd "S12 NBT" 9" W.Spruce S28W 24.95' "S11 NBT" Cedar 4x4 post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1975 NBT.	(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Maple N68E 21.4' mrkd "1/16S BT" 8" Spruce S36E 31.3' do 4" Hemlock S34W 22.3' do 9" Sugar N41W 5.3' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/29/06

For the Michigan Department of Natural Resources, Office of Land and Facilities