

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>33W</u>	<u>K2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>48N</u> R <u>33W</u>	<u>16</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Oct 25 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K2) Quarter corner common to Sections 1 and 2. 1852 - Established by Francis Houck, Deputy Surveyor: "South corrected between Sections 1 and 2 ...37.50 set qr. post. Fir 10 N70W 6 links, Fir 12 S45E 16 links. ...77.50 Corner of Sections 1-2-11-12". 1975 - K.L.Sackett RLS states: "Original monument and accessories not found. Reestablished 9-19-75 on line between section corners north and south. Set 1"IDx36" iron pipe with 4" aluminum cap. 16" Elm N82W 17.0', 11" Maple N64E 19.6'." (16-Sec. 2) East 1/16 corner between Sections 2 and 11. 1975 - Established by K.L.Sackett RLS on line between Section corner east and 1/4 corner west. Set 1"IDx24" iron pipe with 4" aluminum cap 21.0 feet south of C/L US41. 5" Cedar S35E 64.2', 5" Cedar S56W 84.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K2) Found the 1975 monument in good condition and at record bearing and distance from the 1975 witnesses, both now dead standing stubs with scribing visible. I found the monument to be 0.78' south and 0.28' west of the prorated original position and I accept same as a careful and faithful reestablishment of the position of the original corner. (16-Sec. 2) Recovered the 1975 monument flush with shoulder of highway US41. Cap is illegible due to corrosion and dirt. The 1975 witness Cedar trees were found at record bearing and distance. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K2) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Maple N44E 29.8' wrkd "1/4S NBT" 9" dbl Y.Birch S42E 12.6' do 6" Y.Birch S56W 27.5' do 10" Sugar N73W 26.9' do Cedar 4x4 post adjacent. Bearings are magnetic. Distances are to nail with tag.	(16) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" Cedar S29E 64.1' old marks * 8" Cedar S61W 85.0' do * 3" B.Ash S08E 56.0' wrkd "1/16S BT" 7" B.Ash S11W 52.5' do Cedar 4x4 post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1975 NBT.
---	---

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2	●	1	
3											●		
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/29/06