

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 48N R 33W

K13

T R

T R

S T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims

May 18 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K13) Corner common to Sections 35 & 36 T48N-R33W and Sections 1 & 2 T47N-R33W. 1846 - Established by Austin Burt, Deputy Surveyor: West on South side of Section 36 ...80.00 Set spruce post corner of Sections 35 & 36. Spruce 10 N67E 53 links, Spruce 7 N28W 10 links. 1851 - Additional BTs by Francis Houck, Deputy Surveyor: Spruce 8 S10W 15 links, Tamarack 8 S44E 30 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K13) Found the remains of an old post lying down under 4" of water and muck beneath 6" of sphagnum moss. The point of this post was recovered intact and in a vertical position. The post point is record bearing and distance from the remains of a spruce stump, rotted at surface but solid below the ground water level, with no markings. The other BTs were not recovered. A newer standing spruce post was found adjacent, presumably placed in 1981, that being the date on a Champion Timberlands location poster found on a nearby downed tree. From the post point, true bearing and distance East to a probable original corner is S89 deg. 44'21"E 5278.15' (rec. East 80.00 chains) and West to an original corner is N89 deg. 54' 20"W 5280.50' (rec. West 80.00 chains). I accept the post point as the best available evidence of the position of the original corner and replace it with a monument as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K13) Set 1"IDx48" I.pipe with 4" alum.
 MDNR cap, made firm with 2' long
 tamarack hubs. Set measuring nails in:
 4" Tamarack S37E 98.7' wrkd "S1 NBT"
 5" Tamarack S02W 87.0' "S2 NBT"
 8" Tamarack S60W 106.7' "S2 NBT"
 4" Tamarack N42W 72.0' "S35 NBT"
 Set a sq'd tamarack post adjacent.
 Bearings are magnetic. Distances are to
 nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/05

For the Michigan Department of Natural Resources, Office of Land and Facilities