

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>48N</u> R <u>33W</u>	M10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 02 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(M10) Quarter corner common to Section 25 T48N-R33W and Section 30 T48N-R32W. 1846 - Established by Austin Burt, Deputy Surveyor: North on East side of Section 25 ...40.00 Set Sugar post Qr. Section corner. Y.Birch 10 S32 1/2E 46 links, Sugar 7 N21W 56 links. ...80.00 Section corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M10) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record between Section Corners M9 2638.62' north and M13 7915.86' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 12" Sugar S03E 8.2' wrkd "1/4S NBT"
 7" Sugar in clump N24E 24.9' do
 6" Sugar S53W 37.0' do
 10" Sugar in clump M40W 38.0' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/05