

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>48N</u> R <u>33W</u>	<u>M13</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 18 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(M13) Corner to Townships 47 & 48N, Ranges 32 & 33W. 1846 - Established by Austin Burt, Deputy Surveyor: West on South side of Section 36. Set spruce post corner of [Township]. Tamarack 6 N17 1/2E 40 links, Tamarack 14 S68W 21 links. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(M13) Recovered and accepted the point of a spruce post, which I take to be the remains of the original post, about 14" below the ground surface and below the water table, at record bearing and distance from the remains of the probable Tamarack 8Ts. The Tamarack N17 1/2E is a very rotted stump lying under sphagnum moss, solid below the water line, about 12" in diameter, with no markings visible. The Tamarack S68W is a very rotted stump found about 14" below mud level, no markings visible. From the position of the post point, bearing and distance west to a probable original corner is N89 deg. 44'21"W 5278.15 feet (rec. as West 80.00 chains); bearing and distance north to M9 of record is N 0 deg. 05'05"E 10554.50' (rec. as North 160 chains). From the position of the post point, I found a Champion Timberlands location tag on a spruce post 79' north. Placed a monument, described below, at the position of the post point.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(M13) Set 1" IDx48" I.pipe with 4" alum. MDNR cap. Made firm with 2' long cedar hubs. Set measuring nails in:  
 4" Cedar N19E 34.1' mrkd "S31 NBT"  
 9" Cedar S80E 37.5' "S6 NBT"  
 4" Tamarack S05E 15.2' do  
 7" B.Spruce N38W 21.2' "S36 NBT"  
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/27/05