

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>27</u> T <u>48N</u> R <u>33W</u>	<u>6</u>
	S <u>27</u> T <u>48N</u> R <u>33W</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 14 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (6-Sec. 27) Northeast 1/16 corner, Sec. 27. Not established in the original survey.
- (7-Sec. 27) North 1/16 corner between Sections 27 and 26. Not established in the original survey. The official 1853 General Land Office plat describing the subdivision of this township gives the distance to this corner from I9 as 20.00 chains.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6-Sec. 27) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (7-Sec. 27) Established the corner at 20 chains, proportionate to the original record, south of Section corner I9 and on line between I9 and the MC on the north shore of King Lake. The position is 1317.76' South of I9 (GLO plat 20.00 ch.) and 812.40' North of the reestablished MC (GLO plat 12.33 ch.).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (6) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
5" Tamarack N05E 25.3' mrkd "1/16S 8T"
8" Tamarack S30E 65.2' do
5" Tamarack S22W 54.5' do
4" Tamarack N77W 45.8' do
Set sq'd Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (7) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
5" W.Birch N24E 17.6' mrkd "1/16S 8T"
6" Maple N46E 14.1' do
7" W.Birch S49E 5.7' do
9" W.Pine S84W 25.8' do
Set sq'd Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|---|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/05