

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 2 T 48N R 33W	5
	S 2 T 48N R 33W	4
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 26 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (5-Sec. 2) North 1/16 corner, Section 2. Not established in the original survey.
- (4-Sec. 2) Northwest 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (5-Sec. 2) Established the corner on the North-South 1/4 line of Section 2 20 chains, proportionate to the original record, north of the Center of the Section. The position thus being 1322.40' north (GLO 20.00 ch.) of the Center of Section 2 and 1159.42' south (GLO 17.535 ch.) of the Quarter corner common to Section 2 and Section 35, T49N-R33W.
- (4-Sec. 2) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
3" Sugar N10E 23.0' mrkd "1/16S BT"
3" Sugar N51E 26.6' do
3" Sugar S44E 20.7' do
7" Cedar S10W 2.9' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
6" Sugar N14E 24.7' mrkd "1/16S BT"
6" Maple S05W 19.6' do
12" Cedar S56W 44.9' do
10" Sugar N69W 32.5' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|---|--|

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/29/06