

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S 25 T 48N R 33W	8
	S 25 T 48N R 33W	4
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**Register of Deeds Stamp & File  
Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

4 Jun 13 2005  
 8 Jun 02 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- (8-Sec. 25) West 1/16 corner, Section 25. Not established in the original survey.  
 (4-Sec. 25) Northwest 1/16 corner, Sec. 25. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (8-Sec. 25) Established the corner midway and on a straight line between Quarter corner 1322.55' West and Center of Section (not monumented) 1322.55' East.  
 (4-Sec. 25) Established at the intersection of straight lines connecting opposite 1/16 corners. From the position thus established, a Champion Timberlands location poster dated 1/23/80, marked to identify the approximate 1/16 corner, is S80 1/2 deg. W, 243' distant.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |   |
|--|---|
| (8) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>9" Maple N28W 11.1' wrkd "1/16S BT"<br>11" Maple S64E 30.0' do<br>11" Maple S38E 48.3' do<br>11" Maple S81W 13.0' do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (4) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>7" Maple N27W 7.4' wrkd "1/16S BT"<br>4" Maple N06E 17.8' do<br>9" Y.Birch S21E 39.1' do<br>10" Sugar S03E 40.5' do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/27/05