

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>2</u> T <u>48N</u> R <u>33W</u>	<u>8</u>
	S <u>2</u> T <u>48N</u> R <u>33W</u>	<u>6</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Oct 27 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (8-Sec. 2) West 1/16 corner, Section 2. Not established in the original survey.
- (6-Sec. 2) Northeast 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (8-Sec. 2) Established the corner midway and on a straight line between Quarter corner 1320.04' west and Center of Section (unmonumented) 1320.04' east. The corner falls on the sloped edge of a large rock situated just under the ground surface. I bent the pipe at an approximate 45 degree angle and drove it into the ground along the slope of the rock leaving about 12" of pipe projecting vertically at the corner position. Made the monument firm in a small mound of rock.
- (6-Sec. 2) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The monument was driven approx. 6" to refusal and made firm in a 2.8' dia.x1.5' high mound of rock.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
9" Spruce N22E 11.8' wrkd "1/16S BT"
7" Maple S24E 2.3' do
8" Spruce S64W 36.5' do
24" W.Pine N29W 15.8' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap made firm in a mound of rock. Set measuring nails in:
12" Sugar N10W 30.1' wrkd "1/16S BT"
6" Sugar S50E 18.3' do
12" Sugar S15E 20.3' do
11" Sugar S77W 8.7' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|---|---|

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2	1			
3													
4	7		8		9		10		11	12			
5													
6	18		17		16		15		14	13			
7													
8	19		20		21		22		23	24			
9													
10	30		29		28		27		26	25			
11													
12	31		32		33		34		35	36			
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/29/09

For the Michigan Department of Natural Resources, Office of Land and Facilities