

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T. ___ R. ___	_____
	T. ___ R. ___	_____
	T. ___ R. ___	_____
2. Property Controlling in Section	S. ___ T. ___ R. ___	_____
	S. 27 T. 48N R. 33W	8
	S. 27 T. 48N R. 33W	15
3. Miscellaneous Property in Sec.	S. ___ T. ___ R. ___	_____
	S. ___ T. ___ R. ___	_____

**Register of Deeds Stamp & File  
Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

15 Jun 22 2005  
 8 Jul 06 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (8-Sec. 27) West 1/16 corner, Sec. 27. Not established in the original survey.
- (15-Sec. 27) West 1/16 corner between Sections 27 and 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (8-Sec. 27) Established the corner midway and on a straight line between Quarter corner 1320.26' West and Center of Section 1320.26' East.
- (15-Sec. 27) Established the corner midway and on the Section line between Section corner 1323.21' West and Quarter corner 1323.21' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| (8) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>20" W.Pine N01W 37.5' mrkd "1/16S BT"<br>18" W.Pine N45E 28.8' do<br>8" Maple S41E 7.0' do<br>10" W.Pine N45W 34.9' do<br>Set sq'd cedar post adjacent. Bearings<br>are magnetic. Distances are to nail<br>with tag. | (15) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>8" Cedar N76W 6.4' mrkd "1/16S BT"<br>12" Cedar N47E 16.4' do<br>6" Cedar S29E 6.1' do<br>6" Cedar S40W 6.8' do<br>Set sq'd cedar post adjacent. Bearings<br>are magnetic. Distances are to nail<br>with tag. |
|--|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/27/05

For the Michigan Department of Natural Resources, Office of Land and Facilities