

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___
 S 24 T 48N R 33W 11
 S 25 T 48N R 33W 10

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims

Jun 07 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- (11-Sec. 24) Southwest 1/16 corner, Sec. 24. Not established in the original survey.
- (10-Sec. 25) South 1/16 corner between Sections 26 and 25. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (11-Sec. 24) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (10-Sec. 25) Established the corner midway and on line between Quarter corner 1315.84' North and Section corner 1315.84' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (11) Set 1" IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
8" Sugar N70E 36.4' mrkd "1/16S BT"
6" Maple S14W 38.0' do
12" Spruce S63W 29.9' do
7" Maple N23W 9.1' do
Set sq'd Spruce post adjacent. Bearings are magnetic. Distances are to nail with tag. | (10) Set 1" IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
6" Sugar N29E 25.6' mrkd "1/16S BT"
4" Sugar S50E 12.6' do
10" Sugar S52W 4.2' do
11" Sugar N27W 18.5' do
Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|---|---|



1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/05

For the Michigan Department of Natural Resources, Office of Land and Facilities