

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S 24 T 48N R 33W	12
	S 25 T 48N R 33W	1
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 08 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4		3		2		1			
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (12-Sec. 24) South 1/16 corner, Section 24. Not established in the original survey.
- (1-Sec. 25) West 1/16 corner between Sections 24 and 25. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12-Sec. 24) Established the corner midway and on a straight line between Quarter corner 1313.80' South and Center of Section 1313.80' North.
- (1-Sec. 25) Established the corner on the Section line and midway between Section corner 1328.39' West and Quarter corner 1328.39' East. From the position for the corner, I found a squared wood post, apparently placed by a local forester, S89W 157' distant, and I found a Champion Timberlands location poster affixed to a tree, dated 1982, and marked "approx 1/16 corner", S83W 216' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (12) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
8" Cedar N37E 18.2' mrkd "1/16S BT"
7" Cedar S85E 27.0' do
6" Cedar S26W 27.2' do
10" Cedar S60W 21.3' do
Set sq'd Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (1) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
20" Sugar N20E 31.2' mrkd "1/16S BT"
7" Sugar N74E 25.4' do
10" Sugar S04E 18.7' do
9" Sugar N83W 28.1' do
Set sq'd Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|---|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/27/05