

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 33W	MC #3 (Meander Corner on West shore of King Lake between Sections 27 and 34)
	T ___ R ___	
	T ___ R ___	
	S ___ T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on June 22, 20 05 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Meander corner on West shore of King Lake between Sections 27 and 34. 1851 - Established by Francis Houck, Deputy Surveyor: S 89°45'W corrected between Sections 27 and 34 ...34.46 Set Meander Post, W.Pine 4 N67°W 28 links, Spruce 4 S82°W 31 links. ...80.33 Section Corner. S 89°40'W corrected between Sections 28 & 33 ...80.11 Section corner. The original GLO record also notes the bearing on North line Section 27 was S 89°58'W. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner on the Section line between Sections 27 and 34 at the index-corrected GLO distance east of corner G11. The position for the corner is S 89°53'11"E (true) 3022.31' (45.793 ch. M, 45.87 ch. rec. GLO) from G11. The direction of the Section line was reestablished by reference to the line between Sections 28 & 33. Specifically, the observed bearing of the line 28/33 (S 89°58'11"E) was rotated 5 minutes clockwise (that being the difference in GLO record bearing between the two sections lines 28/33 and 27/34) and the line between 27 and 34 was run in on the resulting bearing. This direction also harmonizes with the GLO direction of the line between Sections 22/27. The line between 22/27 is 13 minutes different in bearing from the line between 27/34 in the record and 10 minutes different in bearing as observed on the ground. The index correction for the distance (-9 ft/80 ch.) was based on observation of 8 nearby Section lines. The position for the corner falls in the west edge of King Lake and was not monumented. Placed a WITNESS CORNER monument 2.00' West of the MC position and on the Section line.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 1"IDx32" I.pipe w/4" aluminum MDNR cap with stamping "WITNESS CORNER MC27/34 2.00 FT EAST". Set measuring nails in:  
 3" Spruce N55°W 23.6' mrkd "WC BT"  
 16" W.Pine S68°W 6.6' do  
 17" W.Pine S58°W 15.9' do  
 3" Balsam S26°W 10.0' do  
 Bearings are magnetic. Distances are to nail with tag. Water's edge of King Lake is 1 ft. east of the WC monument.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/6/05