

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~48-49~~ NR. ~~34~~ W. . .

----- Baraga ----- COUNTY

DESCRIPTION OF CORNER Sec. corner for sections ~~4~~ - ~~5~~ - ~~32~~ - ~~33~~ -----

DESCRIPTION OF CORNER MONUMENT 1" pine with 4" brass cap. -----

WITNESSES TO CORNER 4-18-48 -----

White Pine 10" S 10°, E 17 links. Marked "S41BT" ..

White Pine 10" N 57°, W 90 links. Marked "S32BT" ..

Red Pine 10" N 6°, E 194 links. Marked "S33BET" ..

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. This corner was replaced from one white pine bearing tree bearing S 55°, E 20 links. Tree down and rotted. Found both faces and remains of notch at bottom. Found while checking lines run by District Forester, Stevens. ~~Co.~~ lies in marsh. Found old wood post 23 links south of section corner.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler ----- DATE 4-29-59 -----
REGISTERED LAND SURVEYOR