

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 48. NR 34 - 35 W

Baraga COUNTY

DESCRIPTION OF CORNER Sec. corner for Sections 6 - 7 - 1 - 12

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER 4-25-58

14" Jack Pine S 43°, E 100 links. Marked "S7NBT"

8" Red Pine N 71°, E 76 links. Marked "S6NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Replaces as set by U. S. Forest Service. Found wood post and 34" white pine stump N 82°, E 8 links. Stump scribed "S6BT". Very old work. Many white pine stumps in area but could not fit any to corner. Checked distance to streams east, west, and south. Found by Forestry Division Survey Crew.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 4-29-59  
REGISTERED LAND SURVEYOR