

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48-49 NR. 34 W. . .

Baraga COUNTY

DESCRIPTION OF CORNER Sec. corner for sections 5 - 6 - 31 - 32

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER 4-25-58

8" Jack Pine N 74°, W 26 links. Marked "S31NB1"

6" Jack Pine S 16°, W 15 links. Marked "S6NB1"

6" Jack Pine S 78°, E 14½ links. Marked "S5NB1"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Replaced as previously set by unknown surveyor. Found 1" iron pipe and wood post in place. Found no evidence of original corner. Position checks with other corners in area. Corner lies ½ ch. east of road. Corner found by Forestry Division Survey Crew.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 4-29-59
REGISTERED LAND SURVEYOR