

BARAGA Co

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. R. 34 W.	J9
2. PROPERTY CONTROLLING IN SECTION	26 T. 48 N. R. 34 W.	1, 14
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 24, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner J9: Original monument and accessories not found.

Corner 1: Not Set On Original Survey Nor Subsequently Apparently

Corner 14: Not Set on Original Survey Nor Subsequently Apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J9: Re-established on line between section corners east and west. Corner falls 16 ft. north of east-west road.

Corner 1: Established on line between corners east and west.

Corner 14: Established on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner J9: Set 1" I.D.x24" Iron Pipe with 4" aluminum cap.

5" Cedar S24W 48.6 ft. 1/4S, NBT

4" Maple N51E 9.1 ft. 1/4S, NBT

6" Maple N56W 24.4 ft. 1/4S, NBT

Corner 1: Set 1" I.D.x24" Iron Pipe with 4" aluminum cap.

9" Maple N20E 27.3 ft. 1/16S, BT

12" Cedar S03E 32.8 ft. 1/16S, BT

8" Maple N47W 22.5 ft. 1/16S, BT

Corner 14: Set 1" I.D.x24" Iron Pipe with 4" aluminum cap.

6" Cedar S85W 25.2 ft. 1/16S, BT

14" White Pine N52W 78.4 ft. 1/16S, BT

5" Cedar S59E 72.9 ft. 1/16S, BT

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____

CHIEF OF SURVEY PARTY
Keith L. Sackett
MICHIGAN REGISTERED LAND SURVEYOR
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006