

BARAGA Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 48 N. R. 34 E. W.	K12
2. PROPERTY CONTROLLING IN SECTION _____	36, T. 48 N. R. 34 E. W.	10, 3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 21, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 10: Not set on original survey nor subsequently apparently.

Corner 3: Not set on original survey nor subsequently apparently.

Corner K12: Original monument and accessories not found. Found Celotex location poster in 9" Maple S62W 25.1 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 10: Established midway and on line between corners North and South.

Corner 3: Established midway and on line between corners North and South.

Corner K-12: Re-established midway on line between section corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 10: Set 1" I.D.x24" Iron Pipe with 4" aluminum cap buried in old US-141
 10" Sugar N81W 25.9' 1/16S, BT
 8" Sugar S21E 49.9' 1/16S, BT
 6" Sugar N40E 29.4' 1/16S, BT

6" Balsam N50W 37.8 ft. 1/16S, BT
 4" Balsam S75E 38.1 ft. 1/16S, BT

Corner 3: Set 1" I.D.x24" Iron Pipe with 4" aluminum cap buried in west shoulder of old US-141
 9" Maple S59W 18.1 ft. 1/16S, BT

Corner K12: Drove 1" I.D.x24" Iron Pipe into old US-141
 9" Maple S62W 25.1 ft. 1/4S, NBT
 9" Yellow Birch N73E 28.9ft. 1/4S, NBT
 5" Sugar S58E 34.9 ft. 1/4S, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE July 7, 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006