

BARAGA Co

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 48 N. 36 R. 34 W. ^{W.}	I9, K10, K9
2. PROPERTY CONTROLL- ING IN SECTION_____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on May 24, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I9: Original Monument and Accessories Not Found. Found Fence corner formerly witnessed by Michigan State Highway Department.

Corner K9: Original Monument and Accessories Not Found. Found 1" Iron Pipe by unknown length at Int. E, W, S roads.

Corner K-10: Original Monument and Accessories Not Found. Found 1" Iron Pipe by unknown length at Intersection of roads N, S. E.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I9: Re-established at fence corner formerly witnessed by Michigan State Highway Department.

Corner K9: Re-established at Iron Pipe formerly witnessed by Michigan State Highway Department. Fits good with corners north and south.

K-10: Re-established at iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I9: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap.	Corner K10: 1" O.D. Iron Pipe by unknown length.
4" Ash S69E 5.6 ft. S26 NBT	6" Maple S44E 18.1 ft. 1/4S NBT
18" Basswood N61W 24.2 ft. S22 NBT	20" White Pine S28W 34.8 ft. 1/4S NBT
4" Maple S70W 14.8 ft. S27NBT	6" Maple N43W 19.7 ft. 1/4S NBT

K9: 1" I.D. by unknown length Iron Pipe
 10" Maple N29W 4.0 ft. S23 NBT
 8" Maple S13E 7.8 ft. S25 NBT
 5" Maple S47W 45.9 ft. S26 NBT

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE July 14, 1978

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006