

BARAGA Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. N. S., R. E. W.
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S., R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION 24, T. 48, N. X, R. 34, E. X, W.		
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Keith L. Sackett** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **February 28** 19**79**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

These corners witnessed as set by G. A. Shadko, R.L.S., 1934 in January, 1945.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4 corners are bronze plates cemented into top of 4 in. concrete cylinder by 5 ft. long.

Corner A. D.N.R. Reference Tag and Nail	Corner B. D.N.R. Reference Tag and Nail
W. Birch S88E 6.60 ft.	3" Tamarack S41W 18.87 ft.
' Spruce S40E 17.15 ft.	4" Balsam N28E 17.60 ft.
' Maple S70W 23.50 ft.	6" Spruce S50E 17.14 ft.
Corner C. D.N.R. Reference Tag and Nail	Corner D. D.N.R. Reference Tag and Nail
" Cedar N39E 10.53 ft.	8" Maple S49W 13.00 ft.
' Cedar S60E 16.41 ft.	12" Maple N25W 10.85 ft.
' Ash S82W 34.50 ft.	10" Maple N74E 34.25 ft.

SIGNED BY..... DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY..... DATE

APPROVED AND SIGNED BY *Keith L. Sackett* DATE

Keith L. Sackett
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. **19006**

