

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA CO.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 ^{N.} XX R. 34 ^{XX} W.	L11
2. PROPERTY CONTROLLING IN SECTION	36 T. 48 ^{N.} XX R. 34 ^{XX} W.	2,1
3. MISCELLANEOUS PROPERTY IN SECTION	T. ^{N.} S. R. ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 26, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner L11: Original monument and accessories not found.
- Corner 2: Not set on original survey nor subsequently apparently.
- Corner 1: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner L11: Restored on line and midway between corners east and west.
- Corner 2: Established on line and midway between corners east and west.
- Corner 1: Established on line and midway between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner L11: Set 1" I.D. by 36" iron pipe with 4" aluminum cap.
 - 5" Spruce S74°E 7.3 ft. 1/4S, NBT
 - 4" Spruce S30°W 4.5 ft. 1/4S, NBT
 - 4" Spruce N43°W 4.5 ft. 1/4S, NBT
- Corner 2: Set 1" I.D. by 36" iron pipe with 4" aluminum cap.
 - 4" Spruce N84°W 4.8 ft. 1/16 S, BT
 - 4" Spruce N59°E 10.3 ft. 1/16 S, BT
 - 4" Spruce S08°E 13.9 ft. 1/16 S, BT

Corner 1: Set 1" I.D. by 36" iron pipe with 4" aluminum cap.
 9" Spruce S08°E 11.9 ft. 1/16 S, BT
 5" Spruce S71°W 7.9 ft. 1/16 S, BT
 5" Tamarack N60°E 15.6 ft. 1/16 S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-0-80

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006