

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>34W</u>	<u>J3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 01 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


(J3) Quarter corner common to Sections 2-11. 1853 - Established by Francis Colman: [west] Corrected between Sections 2-11...40.08 Set qr. Sec. post. Aspen 12 N78E 32 links, Aspen 12 S49W 25 links. ...80.17 Sec. corner. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original GLO record between reestablished Section corners 2640.05' west and 2639.39' east. From the corner thus established, the approximate centerline intersection of meandering roads north and west is 18' east and 23' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) Set 1" IDx32" I.pipe with 4" alum.
 MDNR cap. Blazed, scribed, and set measuring nails in:
 8" dbl Sugar N47W 49.2' "1/4S NBT"
 7" dbl Y.Birch East 20.8' do
 6" Maple S20E 18.3' do
 7" dbl Maple S28W 26.5' do
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/30/04

For the Michigan Department of Natural Resources, Office of Land and Facilities