

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T. <u>48N</u> R. <u>34W</u>	<u>J1</u>
	T. <u>48N</u> R. <u>34W</u>	<u>I1</u>
	T. <u> </u> R. <u> </u>	<u> </u>
2. Property Controlling in Section	S. <u> </u> T. <u> </u> R. <u> </u>	<u> </u>
	S. <u> </u> T. <u> </u> R. <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S. <u> </u> T. <u> </u> R. <u> </u>	<u> </u>
	S. <u> </u> T. <u> </u> R. <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 01 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (J1) Quarter corner common to Section 2 T48N-R34W and Section 35 T49N-R34W. 1846 - Established by Austin Burt midway between Section corners. Set Ironwood post. Sugar 24 N34E 33 links, Sugar 18 N46W 59 links. Found no subsequent record.
 (I1) Corner common to Sections 2-3 T48N-R34W and 34-35 T49N-R34W. 1846 - Established by Austin Burt: West on South side of Section 35 (T49N-R34W)...80.00 Set Birch post corner of Secs 34&35. W.Birch 8 N60E 15 links, W.Birch 7 N10W 23 links. Additional BTs by Francis Colman 1853: Aspen 8 S30E 2 links, Aspen 8 S35W 25 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J1) The original post and accessories were not recovered. They have likely been destroyed by road building. Reestablished the corner on the township line and midway between reestablished Section corners 2648.72' east and west.
 (I1) The original post and accessories were not recovered. Reestablished the corner on the township line and by single proportionate measurement to the original record between Township corner 10594.88' east and Section corner 10594.88' west. The easting of the position for this corner is consistent with the GLO record with respect to the location of corners I2 (found iron pipe) and I3 (reestablished from local evidence) to the south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (J1) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: | (I1) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: |
| 7" Maple North 21.4' "1/4S NBT" | 13" Hemlock N14E 13.9' "S35 NBT" |
| 5" Sugar S22E 40.8' do | 7" dbl Maple S88E 29.1' "S2 NBT" |
| 6" Maple S23W 48.4' do | 3" Hemlock S27W 19.5' "S3 NBT" |
| 10" Maple West 54.1' do | 10" Spruce S86W 27.1' do |
| Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/30/04

For the Michigan Department of Natural Resources, Office of Land and Facilities