

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>48N</u> R <u>34W</u>	<u>K2</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T <u>48N</u> R <u>34W</u>	<u>7</u>	
	S <u>2</u> T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

Jun 30 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K2) Quarter corner common to Sections 1-2. 1853 - Established by Francis Colman: [south] Corrected between 1&2...37.63 set quarter section post. Y. Birch 12 N64W 17 links, Sugar 8 S88E 12 links. ...77.63 set post cor. of sections 1-2-11-12.
 (7-Sec. 2) North 1/16 corner between Sections 1 and 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K2) The original post and accessories were not recovered. Reestablished the corner on line and by single proportionate measurement to the original record between reestablished corners K1 2477.13' north and K3 2633.14' south.
 (7-Sec. 2) Established the corner at 20 chains, proportionate to the original record, north of K2 and on line between K2 and K1. Distances measured were 1160.56' to K1 and 1316.57' to K2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K2) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 8" Sugar N17E 19.3' "1/4S N8T" 9" Sugar S53E 13.7' do 9" Sugar S04E 7.7' do 9" Sugar N12W 14.0' do Bearings are magnetic. Distances are to nail with tag.	(7) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 8" Sugar N27E 29.7' "1/16S B7" 5" Sugar S51E 14.7' do 7" Sugar S72W 3.3' do 12" Sugar N30W 20.6' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/30/04