

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 34W	I2
	T 48N R 34W	J2
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Jun 29 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (I2) Quarter corner common to Sections 2-3. 1853 - Established by Francis Colman: [south] Corrected between Sections 2&3...38.51 Set quarter Section post. Aspen 10 N52E 16 links, Aspen 8 S42W 16 links ...78.51 Set post corner of sections 2-3-10-11.
- (J2) Center of Section 2. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (I2) The original post and accessories were not recovered. Found and accepted a 1" iron pipe, placed by an unknwn surveyor, which is 2.5' east and 12.7' north of the position proportionate to the original record. Left the monument in place and placed into it a yellow plastic cap stamped "MICH DNR PS33986".
- (J2) Established the corner at the intersection of straight lines connecting opposite quarter corners. From the position thus established, an old fence and stone row, leading east, is 36.5' south, and the center of a N-S gravel road is 22' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (I2) Found 1" ID iron pipe projecting 0.1' above ground. Blazed, scribed, and set measuring nails in: | (J2) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: |
| 4" Sugar N09E 28.1' "1/4S NBT" | 3" Y. Birch N15E 42.2' "C1/4 8T" |
| 12" Spruce S27E 19.6' do | 5" Maple N53E 24.1' do |
| 11" Y. Birch S29W 17.5' do | 5" Sugar S24W 19.2' do |
| 10" Hemlock S80W 36.6' do | 5" Basswood N81W 2.4' do |
- Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.
- Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date B/30/04

For the Michigan Department of Natural Resources, Office of Land and Facilities