

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 48N R 34W	E11
	T 48N R 34W	E12
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

E12 Jun 07 2004
 E11 Jun 08 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E11) Corner common to Sections 28-29-32-33. 1853: Established by Francis Colman: [north] Corrected between Sections 32 and 33...80.26 Set post cor. of Sections 28-29-32-33. Fir 8 N45W 17 links, Cedar 8 S30E 20 links.
 (E12) Quarter corner common to Sections 32-33. Established in 1853 by Francis Colman: [north] Corrected between Sections 32&33...40.13 set quarter section post. Cedar 6 N13E 21 links, Spruce 8 S27W 25 links. ...80.26 Cor. of Secs. 28-29-32-33.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E11) The original post and accessories have been destroyed by road construction and were not recovered. Found and accepted a 1" ID iron pipe, approx. 12" below the road surface, in the intersection of the Maki and Opal Roads. Distances West and South to adjacent corners (2638.39' and 5275.79' respectively) check fairly well with the original record. Left the monument in place and made witnesses as described below.
 (E12) The original post and accessories were not recovered. Reestablished the corner midway and on a straight line between monumented Section corners 2637.89' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E11) Found 1" ID Iron pipe 12" below road surface.	(E12) Set 1" IDx32 I.pipe with 4 alum. MDNR cap. Blazed, scribed, and set measuring nails in:
Address sign post N69E 39.2'	8" B.Spruce N08W 5.5' "1/4S NBT"
Road sign post S11E 7.2'	7" B.Spruce N69E 6.8' do
Telephone post N45W 53.0'	6" B.Spruce S20W 10.4' do
Power pole 99-01422 N22W 54.35' nail and tag.	4" Maple N85W 17.3' do
Bearings are magnetic.	Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/25/04

For the Michigan Department of Natural Resources, Office of Land and Facilities