

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>34W</u>	D12
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>32</u> T <u>48N</u> R <u>34W</u>	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 07 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D12) Center of Section 32. Not established in the original survey.
 (8-Sec. 32) West 1/16 corner, Section 32. Not established in the original survey.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D12) Established the corner at the intersection of straight lines connecting opposite quarter corners.
 (8-Sec. 32) Established the corner midway and on a straight line between Quarter corner 1318.92' West and Center of Section 1318.92' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D12) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 4" B.Spruce S65W 19.1' "C1/4 BT" 17" W.Pine N28W 91.7' do 3" B.Spruce N43E 31.9' do 4" B.Spruce S52E 25.9' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(8) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 5" Balsam N63E 10.7' "1/16S N8T" 5" B.Ash S51E 19.9' do 4" Y.Birch S65W 28.2' do 15" Cedar N74W 53.4' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/25/04

For the Michigan Department of Natural Resources, Office of Land and Facilities