

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 34W	A2
	T 48N R 34W	A3
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 06 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (A2) Quarter corner common to Section 6 T48N-R34W and Section 1 T48N-R35W. 1959 - Reestablished by proportionate measurement and on line between two Section corners by Billy D. Buckler. Set 1" pipe with 4" brass cap. 11" J.Pine N26E 03 links, 9" J.Pine N64W 22 links, 7" J.Pine S15W 17 links.
- (A3) Section corner common to Sections 6-7 T48N-R34W and Sections 1-12 T48N-R35W. 1958 - Remonumented by Billy D. Buckler at position monumented by U.S. Forest Service. Set 1" pipe with 4" brass cap. 14" J.Pine S43E 100 links, 8" R.Pine N71E 76 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (A2) Recovered the 1959 monument in good condition but with a broken cap, at record bearing and distance from the J. Pine SW, now standing dead, and the J.Pine NE, now dead and down. Could not remove the broken cap so removed the entire monument and replaced it with a new monument, described below. The monument is 3.7' NW of the record proportionate position and is accepted as a careful and faithful reestablishment of the position of the original corner.
- (A3) Recovered the 1958 monument in good condition and at record bearing and distance from the remaining 1958 NBT R.Pine NE, now 19" DBH, in good condition with overgrown blazes. The other 1958 NBT was not recovered. Also found a 9" W.Birch with old blazes, perhaps a USFS witness tree, N37W 23.0'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |
|--|--|
| (A2) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>12" J.Pine N60W 14.5' old marks vis. *<br>4" J.Pine N61E 16.1' mrkd "1/4S NBT"<br>11" J.Pine S56E 36.3' do<br>11" R.Pine S60W 26.2' do<br>Set sq'd J.Pine post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1959 NBT. | (A3) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in:<br>19" R.Pine N69E 49.9' old blazes *<br>6" Maple N20E 11.7' mrkd "S6 NBT"<br>9" W.Birch N37W 23.0' old blazes<br>6" Maple S66W 30.5' mrkd "S12 NBT"<br>A metal sign post is N81W 1.4'. Bearings are magnetic. Distances are to nail with tag. * denotes 1958 NBT. |
|--|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/2/06