

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>34W</u>	<u>83</u>
	T <u>48N</u> R <u>34W</u>	<u>81</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

81 Jul 12 2006
 83 Jul 05 2006

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(83) Quarter corner common to Sections 6 and 7. 1853 - Established by Francis Coleman, Deputy Surveyor: N89deg. 49'E corrected between Secs. 6 & 7 ...35.60 Intersect Sturgeon River 100 links C.S.W. Base 27 angle 12° 2 [sic], 1/21 links; 36.81 over river; 37.60 Set qr. Sec. post. Elm 18 N57W 25 links, Elm 10 S72E 91 links; 39.10 Intersect Sturgeon River 150 links C.W.N.W. ...77.60 Sec. corner.
 (81) Quarter corner common to Section 6 T48N-R34W and Section 31 T49N-R34W. 1959 - Reestablished by proportionate measurement and on line between two section corners by Billy D. Buckler. Set 1" pipe with 4" Brass cap. 5" J.Pine S40W 15.5 links, 5" J.Pine N42E 07 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(83) The original post and accessories were not recovered. The single proportionate position for this corner places it north of the Sturgeon River, or very near the northerly edge - a position that cannot be reconciled to the original record. The river shows no sign of having altered its position in the years since the original survey. Consequently, I reestablish the corner according to the best available evidence: at a position in harmony with the calls to the Sturgeon River at 36.81 chains and 39.10 chains. This position is also in substantial accord with the position of the reestablished corner C3 2635.71' east (original rec. dist 2640.0').
 (81) Recovered the 1959 monument in accord with the 1959 witness trees, both dead. The SW NBT is now a windthrow. Determined that the position of the monument is not the proportionate position described in the 1959 record. The monument is located N12E 34.2' from that position. I did not accept the 1959 position, destroyed the 1959 monument, and reestablished the corner at the proportionate position, on the section line between Township corner 2415.43' west and Section corner 2631.90' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(83) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 13" Box elder S62W 3.7' wrkd "1/4S NBT" 6" Box elder S14W 5.6' do 6" Balsam S12E 26.9' do 11" Balsam S70E 28.1' do Set sq'd W.Pine post adjacent. Bearings are magnetic. Distances are to nail with tag.	(81) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" J.Pine S19E 122.90' wrkd "1/4S NBT" 4" W.Pine S24W 185.36' do Set sq'd cedar post N10E 1.00' nail/tag Set sq'd cedar post N81W 1.00' do Bearings are magnetic.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/2/06

For the Michigan Department of Natural Resources, Office of Land and Facilities