

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S 6 T 48N R 34W	9
	S 6 T 48N R 34W	13
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

13 Jul 13 2006
 9 Jul 12 2006

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (9-Sec. 6) East 1/16 corner, Section 6. Not established in the original survey. Found no subsequent record.
- (13-Sec. 6) Southeast 1/16 corner, Section 6. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (9-Sec. 6) Established the corner midway and on a straight line between Center of Section 1309.88' west and Quarter corner 1309.88' east.
- (13-Sec. 6) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
5" W.Pine S27W 38.5' mrdk "1/16S BT"
11" J.Pine S79E 23.6' do
10" W.Pine N18E 74.5' do
12" J.Pine N70W 35.2' do
Set sq'd J.Pine post adjacent. Bearings are magnetic. Distances are to nail with tag. | (13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
16" W.Pine N62E 11.9' mrdk "1/16S BT"
6" Maple S04E 4.2' do
5" Maple S59W 28.8' do
5" Maple N51W 20.0' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/2/06