

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S 6 T 48N R 34W	10
	S 6 T 48N R 34W	12
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 12 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3	•	•											
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (10-Sec. 6) South 1/16 corner between Section 6 T48N-R34W and Section 1 T48N-R35W. Established in 1987 by K.L.Sackett midway and on line between Section and Quarter corners. Set 1"IDx36" I.pipe with 4" aluminum cap. 5" J.Pine N60W 12.9', 3" J.Pine S19E 2.7', 5" J.Pine S60W 16.3', 3" J.Pine Squared N17E 2.4'.
- (12-Sec. 6) South 1/16 corner, Section 6. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (10-Sec. 6) Recovered the 1987 monument in good condition and at record bearing and distance from the 1987 witnesses, all now dead and down. Measured to Section and Quarter corners South and North and found this monument to be 0.36' from the midway position of record. Accepted same as a careful and faithful determination of the position of the corner.
- (12-Sec. 6) Established the corner midway and on a straight line between Center of Section 1361.19' north and Quarter corner 1361.19' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| (10) Found 1"ID I.pipe with 4" MI Dept. of Conservation cap. Set measuring nails in:<br>5" W.Pine N27W 24.9'    mrkd "1/16S BT"<br>4" W.Pine N45E 27.8'    do<br>6" Spruce S55E 27.2'    do<br>3" Maple S03W 14.0'    do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>5" W.Pine N34E 47.7'    mrkd "1/16S BT"<br>8" Spruce S32E 37.2'    do<br>11" R.Pine West 30.2'    do<br>14" W.Pine N68W 37.1'    do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/2/06