

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 34W	I12
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/26/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I12) Quarter corner common to Sections 34 and 35. 1853 - Established by Francis Coleman, Deputy Surveyor, midway and on the Section line between Section corners 40.195 chains north and south. Ironwood 8" N24E 9 links, Sugar 10" S51W 9 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I12) The original post and accessories were not recovered. Found the rotting remains of an old squared post, estimated to be approx. 60 years old, adjacent to the position subsequently monumented. Found no other evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners of record 2646.81' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap made firm in a mound of rock.
 Set measuring nail with MDNR tag in the side of:
 12" Sugar N42E 22.85' mrkd "1/4S NBT"
 9" Sugar S44E 8.9' do
 8" Sugar S28W 8.0' do
 9" Sugar N61W 10.9' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/24/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities