

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

BARAGA COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. 31 R. X	K 13 K 12
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

BARAGA

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 2-17-83, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner K-13: Original monument and accessories not found. Found old post in marsh which matches original calls.
 - Corner K-12: Original monument and accessories not found.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner K-13: Restored at old post in marsh.
 - Corner K-12: Restored midway and on line between section corners north and south.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner K-13: Set 1" I.D. by 32" I.P. with 4" alum, cap.
10" R. Pine N06E, 85.6 ft. S36, NBT
6" Spruce N61E 55.9 ft. S36, NBT
 - Corner K-12: Set 1" I.D. by 32" I.P. with 4" alum. cap.
8" W. pine S41W 17.7 ft, 1/4S, NBT
7" Maple N55W, 20.8 ft., 1/4S, NBT
7" Maple S75E 16.9 ft. 1/4S, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006